

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163 21,842-0000

LEASE NAME Griffith

WELL NUMBER #9

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 30 TWP. 7 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 12/16/82

Plugging Commenced 8/29/00

Plugging Completed 8/29/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Black Diamond Oil

ADDRESS PO Box 641, Hays, KS. 67601-0641

PHONE/(785) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/14/00 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? Attached to well plug. app.

Producing Formation L-KC/Arb/Topeka Depth to Top 2740 Bottom 3290 T.D. 3308

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	Oil/Water	2713	2922			
Lansing KC	Oil/Water	2969	3194	8 5/8"	1237'	0
Arbuckle	Water	3252	TD	5 1/2"	3327'	2420

9-19-2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Sanded bottom. Sand at 2,692. Bailed 5 Sacks of Portland. Shot 2420'. Pulled to 1770. Pumped 110 sacks 3 huls Pulled to 900'. Pumped 40 sacks 1 hul. Pulled to 450'. Circulated cement to surface with 85 sacks. Pulled the rest of casing hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 E. Main St. Sterling, KS 67579


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641



Subscribed and Sworn to before me this 15<sup>th</sup> day of September, 2000

Verda M. Brin Notary Public

My Commission Expires: 7-18-2003

