

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-163-21413 0000

LEASE NAME Griffeth

WELL NUMBER 6

330 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 30 TWP. 7 RGE. 17 (E) or (W)

COUNTY ROOKS

Date Well Completed _____

Plugging Commenced 12-19-02

Plugging Completed 12-19-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BLACK DIAMOND OIL, INC.

ADDRESS P.O. BOX 641

PHONE# (785) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/11/02 (date)

by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? SENT WITH APPLICATION

Producing Formation ARBUCKLE Depth to Top 3240 Bottom NA T.D. 3292

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil/Water	0	1236	8-5/8	1236	0
		0	3251	5-1/2	3251	1200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 3100 Cir. 15% with 50 sks cement with 250# hulls
Pulled tubing to 1300 Cir. 7% Gel with 40 sks cement with 250# hulls
Pulled tubing to 500 Cir with 150 sks cement to surface
Pulled tubing and top off with 10 sacks cement

Name of Plugging Contractor Chitos Well Service License No. _____

Address P.O. Box 181, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641

MAR 11 2003

KCC WICHITA SUBSCRIBED AND SWORN TO before me this 28th day of February, 2003



[Signature]
Notary Public Verda M. Brin

[Signature]

ALLIED CEMENTING CO., INC. 11327

Federal Tax I.D. [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>12-19-02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>8:30 AM</u>	JOB START <u>12:00 AM</u>	JOB FINISH <u>2:30 PM</u>
LEASE <u>GRIFFIN</u> WELL # <u>6</u>			LOCATION <u>STOCKTON SS. 1 1/2 E.</u>		COUNTY <u>ROCKS</u>	STATE <u>KS</u>	
<u>OLD</u> OR NEW (Circle one)							

CONTRACTOR CHITAS
 TYPE OF JOB PTA
 HOLE SIZE _____ T.D. _____
 CASING SIZE _____ DEPTH _____
 TUBING SIZE 2 1/2 DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT
 AMOUNT ORDERED 250 60/40 10% GEL
22 GEL 500# HULLS

COMMON	<u>150</u>	@	<u>6.65</u>	<u>997.50</u>
POZMIX	<u>100</u>	@	<u>3.55</u>	<u>355.00</u>
GEL	<u>40</u>	@	<u>10.00</u>	<u>400.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>250</u>	@	<u>1.10</u>	<u>275.00</u>
MILEAGE	<u>44/51/1/10</u>			<u>400.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER MARK
 # 346 HELPER DOVE
 BULK TRUCK
 # 213 DRIVER BRENT
 BULK TRUCK
 # _____ DRIVER _____

TOTAL 2517.00

REMARKS:

15 GEL - 50 CCM w/250# HULLS @ 3100
7 GEL - 40 CCM w/250# HULLS @ 1300
60 SILS @ 500' - CONC CEMENT
TBD off w/10 SILS

SERVICE

DEPTH OF JOB	_____		
PUMP TRUCK CHARGE	_____		<u>475.00</u>
EXTRA FOOTAGE	_____	@	
MILEAGE	<u>40</u>	@	<u>3.00</u> <u>120.00</u>
PLUG	_____	@	
	_____	@	
	_____	@	

TOTAL 595.00

CHARGE TO: BLACK DIAMOND
 STREET _____
 CITY RECEIVED STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

MAR 11 2003

KCC WICHITA

To Allied Cementing Co., Inc.