

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

SEP 19 2005

KCC WICHITA

Form CP-4  
December 2003

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.

Address: P.O. Box 352, Russell, KS 67665

Phone: (785) 483-3144 Operator License #: 5135

Type of Well: D & A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: District #1 (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 135-24,378-00-00

Lease Name: Gross

Well Number: #1

Spot Location (QQQQ): App. - NE - NE - SE  
2150 Feet from  North /  South Section Line

360 Feet from  East /  West Section Line

Sec. 4 Twp. 20S S. R. 22  East  West

County: Ness

Date Well Completed: 8-30-05

Plugging Commenced: 5:00 A.M., 8-30-05

Plugging Completed: 8:00 A.M., 8-30-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	243'	8-5/8"	243'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 1530' w/50 sks. cement; 2nd plug @ 780' w/80 sks. cement; 3rd plug @ 270' w/50 sks. cement; 4th plug @ 60' w/20 sks. cement; 15 sks. cement in rathole & 10 sks. cement in mousehole

TOTAL: 225 sks. 60/40 Pozmix, 6% gel w/1/4# flo-seal per sack

Name of Plugging Contractor: Allied Cementing Company, Inc. Sterling Drilling Co. License #: 5142

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.

State of Kansas County, Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 15th day of September, 20 05

Margaret A. Schulte My Commission Expires: \_\_\_\_\_  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 My Appt. Exp. 1-27-09



*KCC  
SEM  
9-22-05  
RBDMs  
CP 2/3*

*Bm*