

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-163-20563-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 13 TWP. 7s RGE. 17w E/W
 Location as in quarters or footage from lines:
 SW SW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Raymond Oil Company, Inc.
 Lease Name Casad #1 Well No. _____
 Office Address One Main Place, Suite 900, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 12/1/82
 Plugging completed 12/6/82
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammell
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3310'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1160'	none
				4 1/2"	2983'	1103'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Surface was flowing. Pushed plug & it stopped at 1196'. Allied pumped 50 barrells of water down well. Plug was gone. Pumped 30 sacks common cement & wiper plug down, stopped at 1278'. Shot at 1102', pulled total of 35 joints. Plugged well with 50 cement, 1 hull, 6 gel, 70 cement, 1 hull, 8 gel, 1 hull, plug, & 70 cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks, 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 82



Irene Hoover
 Notary Public
 STATE OF KANSAS

My Commission expires:

DEC 20 1982
 12-20-1982
 CONSERVATION DIVISION
 Wichita, Kansas