

LEASE NAME Miller

WELL NUMBER 7

2300 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 18 TWP. 7 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 10/17/1983

Plugging Commenced 9/6/2000

Plugging Completed 9/7/2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Black Diamond Oil

ADDRESS P.O. Box 641, Hays, Ks. 67601-0641

PHONE# (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well OIL

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/31/2000 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Arbuckle - KC Depth to Top 2952 Bottom 3287 T.O. 3378

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
<u>Arbuckle - KC</u>	<u>Water</u>	<u>3364</u>	<u>3378</u>	<u>8 3/4"</u>	<u>1,288</u>	<u>10-12-2000</u>
<u>Arbuckle - KC</u>	<u>Oil/Water</u>	<u>2952</u>	<u>3287</u>	<u>5 1/2"</u>	<u>3,375</u>	<u>2536</u>

CONSERVATION DIVISION
 Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set sanded bottom. Boiled 5 sacks of Portland. Shot 2,536'. Falled to 1,690'. Pumped 110 sacks with 3 huls. pulled to 970'. Pumped 40 sacks and 1 hul. pulled to 570'. Circulated cement to surface with 75 sacks. pulled the rest of pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 East Main Street, Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil


STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641, Hays, KS 67601

Subscribed and sworn to before me this 8th day of October, 2003



Verda M. Brin
 Notary Public

My Commission Expires: 7-18-2003
 USE ONLY ONE SIDE OF EACH FORM

