

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1972
07-19-1972
CONSERVATION DIVISION
Wichita, Kansas

15-163-20451-00-00

Lease Owner Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202
Lease (Farm Name) MC REYNOLDS Well No. 1
Well Location NW NW NE Sec. 9 Twp. 7S Rge. (E) 17 (W)
County Rooks Total Depth 3340 Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log filed with application as required Yes
Date and hour plugging is desired to begin 2:00 p.m. 7-13-72

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Norman Cook Address Great Bend, Kansas 67530

Plugging Contractor Abercrombie Drilling, Inc. License No.


Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent
Jerry A. Langrehr, Vice President
Date: July 18, 1972

CONTRACTOR'S WELL LOG

15-163-20451-00-00

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	MC REYNOLDS #1
LOCATION:	NW NW NE, Sec. 9-7S-17W Rooks County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	July 7, 1972
COMPLETION DATE:	July 13, 1972

0	45	Rock
45	150	Clay & Sand stringer
150	365	Shale
365	510	Sand
510	730	Shale
730	910	Sand
910	1224	Shale
1224	1256	Anhydrite
1256	2160	Shale
2160	2420	Shale & Lime
2420	2764	Lime & Shale
2764	2900	Lime
2900	2990	Lime & Shale
2990	3340	Lime
	3340	Rotary Total Depth

Drilled 240' of 9-7/8" surface hole and set 7" - 17 lb. csg. at 1230'. Cemented w/200 sx. common cement w/2% gel and 2% ca.cl. and 175 sx. Sunset cement. Cement circulated. Plug was down at 9:15 a.m. 7-7-72.
Dry and Abandoned

<u>ELECTRIC LOG TOPS</u>		<u>ELEVATION</u>
Topeka	2734 (- 878)	1856 K.B.
Heebner	2942 (-1086)	1854 D.F.
Toronto	2968 (-1112)	1848 G.L.
Lansing	2989 (-1133)	
B/K.C.	3222 (-1366)	
Arbuckle	3312 (-1456)	
ELTD	3340 (-1484)	

RECEIVED
 STATE CORPORATION COMMISSION
 07-19-1972
 JUL 19 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MC REYNOLDS #1, NW NW NE, Section 9-7S-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 17th day of July, 1972.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975

State of Kansas



15-163-20451-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

July 18, 1972

WELL PLUGGING AUTHORITY

Well No.	1
Lease	McReynolds
Description	NW NW NE Sec. 9-7-17W
County	Rooks
Total Depth	3340'
Plugging Contractor	Co. Tools

Abercrombie Drilling, Inc.
801 Union Center Building
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,



J. Lewis Brock, Administrator

Mr. Leo Massey, P. O. Box 582, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.