

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15-163-20818-00-00 (of this well)  
Lease Owner Martin Oil Company  
Address 527 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Casad Well No. 4  
100'N  
Well Location SW NW NW/4 Sec. 13 Twp. 7S Rge. (E) 17 (W)  
County Rooks Total Depth 2716' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin July 9, 1978, 10:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Martin Oil Company

Address 527 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent

Date: July 12, 1978  
Assistant Secretary-Treasurer

RECEIVED  
License No.  
STATE CORPORATION COMMISSION  
07-13-1978  
JUL 13 1978

CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR: Martin Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Casad #4  
 LOCATION: 100'N SW NW NW/4 Section 13-7S-17W  
 Rooks County, Kansas  
 SPUD DATE: July 3, 1978  
 COMPLETION DATE: July 9, 1978

0	225	Surface soil, shale & sand
225	635	Shale & sand
635	1176	Shale
1176	1210	Anhydrite
1210	1736	Shale
1736	2002	Lime & shale
2002	2580	Lime & shale
2580	2716	Lime
	2716	Rotary Total Depth

Spud hole at 8:00 p.m., July 3, 1978. Drilled 1185' of 12 1/4" hole. Ran 29 joints of 8-5/8" surface casing (23#). Set at 1185' with 425 sacks, 250# Halliburton Lite and 175 sacks common, 3% CaCl, 2% gel. Cement did circulate. Job complete at 8:00 a.m., July 5, 1978.

T.D. 2716'. Set first plug at 420' with 40 sacks, second plug at 40' with 10 sacks, common cement. Job complete at 10:00 a.m., July 9, 1978. State Plugger - Leo Massey.

SAMPLE TOPS:

Anhydrite 1177' (+ 626)  
 B/Anhydrite 1210' (+ 593)


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Casad #4, 100'N SW NW NW/4 Section 13-7S-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 12th day of July, 1978.



Sandra Richman  
 Sandra Richman, Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 13 1978

CONSERVATION DIVISION  
 Wichita, Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

July 12, 1978

15-163-20818-00-00

WELL PLUGGING AUTHORITY

Well No.	4
Lease	Casad
Description	100'N SW NW NW Sec. 13-7-17W
County	Rooks
Total Depth	2716
Plugging Contractor	Abercrombie Drilling


Martin Oil Co. &  
Pate-Dombaugh  
527 Union Center  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above named well.