

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
OCT 05 1977  
10-05-977  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 -163 -20732-00-00 (of this well)  
Lease Owner Martin Oil Company  
Address 527 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Ballard Well No. 1  
Well Location NE NW SW Sec. 13 Twp. 7 S Rge. (X) 17 (W)  
County Rooks Total Depth 2893 Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin September 27, 1977, 1:30 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address 38 Walnut Dr., Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Martin Oil Company

Address 527 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent  
Jack L. Partridge, Ass't. Sec.-Treas.  
Date: September 30, 1977

OPERATOR: Martin Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Ballard #1  
 LOCATION: NE NW SW Section 13-7S-17W  
 Rooks County, Kansas  
 SPUD DATE: September 22, 1977  
 COMPLETION DATE: September 27, 1977

|      |      |                      |
|------|------|----------------------|
| 0    | 200  | Surface clay & sand  |
| 200  | 419  | Sand                 |
| 419  | 555  | Sand & shale         |
| 555  | 683  | Pyrite, sand & shale |
| 683  | 805  | Sand                 |
| 805  | 1117 | Shale & red beds     |
| 1117 | 1147 | Anhydrite            |
| 1147 | 1976 | Shale                |
| 1976 | 2400 | Lime & shale         |
| 2400 | 2893 | Lime                 |
|      | 2893 | Rotary Total Depth   |

Drilled 1123' of 12 1/4" hole, ran 8 joints of 8-5/8" surface casing, set at 1119' K.B. Cemented with 315 sacks lite cement and 175 sacks common cement, 3% CaCl, 2% gel. Plug was down at 6:50 p.m., September 22, 1977. Cement did circulate.

T. D. 2893'. Set 1st plug at 360' with 40 sacks, 2nd plug at 40' with 10 sacks. Plug was down at 1:30 a.m., September 27, 1977. State Plugger - Leo Massey.

SAMPLE TOPS:

Anhydrite 1117'  
 B/Anhydrite 1147'

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 05 1977

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Ballard #1, NE NW SW Section 13-7S-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 30th day of September, 1977.

Sandra Richman  
 Sandra Richman, Notary Public



My commission expires July 21, 1979.

State of Kansas



15-163-20732-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

September 29, 1977

WELL PLUGGING AUTHORITY


|                     |                        |
|---------------------|------------------------|
| Well No.            | 1                      |
| Lease               | Ballard                |
| Description         | NE NW SW Sec. 13-7-17W |
| County              | Rooks                  |
| Total Depth         | 2893                   |
| Plugging Contractor | Abercrombie Drilling   |

Martin Oil Co.  
and Pate-Dombaugh Petroleum  
527 Union Center  
Wichita, Kansas 67202  
Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above named well.