

State of Kansas



15-163-20103-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
4-22-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Slaughter of Dreiling Drlg. has this

date requested permission to plug the following described well:

Mr. Slaughter guarantees payment of the plugging fee.

Operator's full Name: Home Stake Production Co.,

Complete Address: Philtower Bldg., Tulsa, Okla.

Lease Name: Stambach Well No. 1

Location: NE NW SW Sec. 33 Twp. 7 Rge. 17 (E)(W)

County Rooks Total Depth 3115' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Slaughter was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720° and displace  
30 sc cement thru drill pipe. Heavy mud to 210° set cementing plug and  
displace 30 sc cement thru drill pipe. Heavy mud to 30° set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Bro Massey  
Conservation Division Agent