

State of Kansas



15-163-20556-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
1975
2-7-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B&B Drlg. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Pate-Dombaugh & Martin Exp.

Complete Address: 502 Union Center, Wichita, Ks.

Lease Name: Roelfs Rolfe Well No. 1

Location: SE SE NW Sec. 31 Twp. 7 Rge. (E)(W) 17

County: Rooks Total Depth 3455' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud
to 40' set solid bridge & 10 sk cmt to base of cellar.

Very truly yours,

Boaz Massey
Conservation Division Agent