

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-23088-00-00

LEASE NAME Aymx

WELL NUMBER 1-13

720 Ft. from S Section Line

1,470 Ft. from E Section Line

SEC. 13 TWP. 10S RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 9-8-05

Plugging Commenced 9-8-05

Plugging Completed 9-8-05

RECEIVED  
SEP 21 2005  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days.

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 1459, Plainfield, IL 60544

PHONE/(815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-8-05 (date)

by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 4,185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	234'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so  
Push plug to 1,925', pump 25 sax cement on plug thru drill pipe; push plug to 1,025', pump 100 sax cement on plug thru drill pipe; push plug to 285', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~operator~~) or (~~operator~~) Contractor above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Jack P Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 19th day of September, 2005

My Commission Expires:



Ruth Phillips  
Notary Public




# Shields

Russell, Kansas

## WELL LOG

Operator: Russell Oil, Inc.  
 Well: Aymx #1-13  
 Commenced: September 1, 2005  
 Completed: September 8, 2005  
 Contractor: Shields Drilling Co.

Well Description: 720' FSL, 1,470' FEL  
 Sec. 13-10S-23W  
 Graham Co., KS



Elevation: 2,358' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	234'	Cmtd. w/175 sax

..... Figures Indicate Bottom of Formations .....

Surface clay, sand, shale	237'
Shale	400'
Shale & sand	1,430'
Sand	1,610'
Shale, sand, redbed	1,835'
Shale	1,904'
Anhydrite	1,944'
Shale	3,140'
Shale & lime	3,305'
Shale	3,660'
Lime	3,973'
Conglomerate, dolomite	4,100' RTD

RECEIVED  
 SEP 21 2005  
 KCC WICHITA

Notes