

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION RECEIVED**  
**OIL & GAS CONSERVATION DIVISION**  
**WELL PLUGGING RECORD**  
 K.A.R. 82-3-117

Form CP-4  
 December 2003  
 Type or Print on this Form  
 Form must be Signed  
 All blanks must be Filled

**KCC WICHITA**

Lease Operator: Berexco  
 Address: Box 723 Hays KS 67601  
 Phone: (785) 628-6101 Operator License #: 5363  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 7-25-05 (Date)  
 by: Jay Pfeifer (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
ARB Depth to Top: 3218 Bottom: 3223 T.D. 3223  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-167-21710 - 00-00  
 Lease Name: Rexroat  
 Well Number: B 3  
 Spot Location (QQQQ): SW - NE - SW -  
1650 Feet from  North /  South Section Line *KCC BEM 10-3-05*  
3630 Feet from  East /  West Section Line *RBDMS CP 2/3*  
 Sec. 30 Twp. 14 S. R. 14  East  West  
 County: Russell  
 Date Well Completed: 5-15-81  
 Plugging Commenced: 7-27-05  
 Plugging Completed: 7-30-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARB	oil, water 3218-3223	0	806	8 5/8	5-15-81	-
		0	3218	5 1/2	5-15-05	
		0	2100	5 1/2		7-30-05

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dump 5400 # sand down 5 1/2 Dug bigger pit & line it. Circ sand out of casing to 150', fell through. Ran tubing to bottom, tag sand @ 2992. Lay down joint. Rig up Allied Cementing  
 Spot 20 sxs 60/40 poz 10% gel w/ 100# hulls @ 2955. Pull tubing out of hole rig up Perf Tech. Shot off casing @ 2100' worked casing free. Lay down 3 joints casing. Continued pulling  
 5 1/2 casing. Pull bottom of casing to 1462. Rigged up Allied, spot 100 sxs 60/40 poz 10% gel w/ 300# hulls. Pull casing to 822' spot 40 sxs 60/40 poz 10% gel w/ 100# hulls.  
 Pull casing to 158' circ. cement to surface w/ 40 sxs. Pull casing out of hole. Top off 8 5/8 surface pipe w/ 5 sxs cement.


Name of Plugging Contractor: Berexco License #: 5363 99998  
 Address: Box 723 Hays KS 67601

Name of Party Responsible for Plugging Fees: Berexco, Inc.  
 State of KS County, Ellis, ss.

Dennis Kirmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dennis Kirmer  
 (Address) Box 723 Hays KS 67601

SUBSCRIBED and SWORN TO before me this 22 day of September, 2005



Shanna Miller My Commission Expires: 9/19/09  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*bu*