

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED SEP 26 2005 KCC WICHITA Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Resource Operations, Inc.

Address: P.O. Box 466 Chase, Kansas 67524

Phone: (620) 938-2983 Operator License #: 30364

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-159-21,652-00-00

Lease Name: Chappelle 1 KCC BEM 9-30-05 PBOOMS Wanted

Well Number:

Spot Location (OOQQ): SE - NE - SE

1980 Feet from North / X South Section Line

330 Feet from X East / West Section Line

Sec 20 Twp 19 S. R. 9 East X West

County: Rice

Date Well Completed:

Plugging Commenced: 9-12-05

Plugging Completed: 9-13-05

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing data: 8-5/8" 224' None, 5-1/2" 3330' 1250'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Plugged off bottom with sand to 3180' and 5 sacks cement. Cut casing loose @1250', layed casing down, full of holes. Ran 1200' of 2-3/8" tubing, pumped 35 sacks cement, pulled tubing up to 800', pumped 35 sacks cement, pulled up to 275' and circulated 120 sacks to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Resource Operations, Inc.

State of Kansas County, Rice ss. Mike Kelso

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 23rd day of September 20 05

[Handwritten Signature] Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]