

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20203-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 31-4S-26W
4620 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ACKERMANN Well #: 2
County: DECATUR Total Vertical Depth: 3705 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3698	0	250 SX CMT
SURF	10.75	225	0	175 SX CMT

\$120⁴¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2005 11:30 AM
Plug Co. License No.: 31660 Plug Co. Name: ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-6924

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2005 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

10 3/4" surface casing set at 225' w/175 sxs cement.
5 1/2" production casing set at 3698' w/250 sxs cement.
PBTd 3698'. TD 3705'.
Perforated 5 1/2" production casing at 2090' - 1400' - 275'.
Ran tubing to 2050' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 600' - pumped 50 sxs cement with 100# hulls - cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Connected to 10 3/4" surface casing - pumped 55 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3620	3622		
3592	3594		
3552	3552		
3551	3553		
3543	3545		
3520	3520		
3518	3522		

Remarks: ALLIED CEMENTING COMPANY-TICKET #19833.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

RECEIVED

DATE 10-3-05

OCT 03 2005

INV. NO. 2006060580

KCC WICHITA

Form CP-2/3

SEP 26 2005

INDEXED


R. W. SHIELDS &
E. K. EDMISTON
WICHITA, KANSAS
CONTR JOHN O. FARMER, INC.

#2 ACKERMANN
31-4-26W
C. W/2 NW NW

CTY DECATUR

GEOL BILL IVERSEN
E 2595 KB CM 12/13/70
API 15-039-20,203

FIELD JENNINGS EXT.
P 20BOPD + 75% WTR
IP LANS 3520, 3543 &
3552, 3592-94 &
3620-22



LOG TOPS DEPTH DATUM 10 3/4" 225/175sx; 5 1/2" 3698/250sx

LOG TOPS	DEPTH	DATUM	DESCRIPTION
*ANHY	2101	+ 494	NO DSTS
TARK	3192	- 597	
HOW	3284	- 689	MICT, PF 8/3620-22, 8/3592-94, NSN, A250MA SWB TO 500'
HEEB	3475	- 880	OB SI/12HRS FU 500' FL SWB DWN-GSO, RE-AC 1500; SWB 1 1/2"
TOR	3502	- 907	RFPH 50% OIL SD/12HRS FU 4.17BF/12HRS RE-SET PLUG, PF
LANS	3516	- 921	3520, 3543, 3552 A2000(PKR LEAKED)RE-AC 2000, PF 8/
LTD	3662	-1067	3543-45 SWB LD, BP 3310, PF 3284-88 GSO, A500, SD/12
RTD	3705	-1110	HRS FU 1200' FIH, SWB 880 & 22BW A1500, SD/12HRS FU
*SAMPLE TOP			1400' FIH, SWB 2 1/2 BF 30% OIL/1HR SWB 3BF 27% OIL/2ND HR
			FU 1200' FL SWB DWN & SWB 35BF(9 80 ON TOP), POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS