

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06015-00-01
Spot: NENENW Sec/Twnshp/Rge: 33-11S-19W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SOLOMON Well #: 1-A
County: ELLIS Total Vertical Depth: 1160 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 221 S. BROADWAY
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3621	0	
SURF	10.75	350	0	

\$ 37⁷⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2005 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CARL GILPIN Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-1883

Proposed Plugging Method: Ordered 125 sxs cement and 500# hulls.
From 0' to 500' no casing - pulled out when plugged in 1946.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2005 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 700' - spotted 50 sxs cement with 200# hulls.
Pulled tubing to 405' - spotted 40 sxs cement with 150# hulls.
Pulled tubing to 30' - spotted 10 sxs cement with 50# hulls.
Total of 100 sxs 60/40 pozmix - 10% gel - 1/4# flocele per sack - 400# hulls.

Perfs:

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L Moses
(TECHNICIAN)

Handwritten initials

INVOICED
DATE 10-3-05

RECEIVED
OCT 03 2005

Form CP-2/3

SEP 29 2005

WELL NO. 2006060581 KCC WICHITA

TRANSWESTERN OIL CO

#1 SOLOMAN

33-11-19W
NE NE NW

Contr.

ELLIS County

E 2125

Comm 8-7-37

Comp. 9-6-37

IP

851 BOPD

Tops	Depth	Bottom
ANH	1403	
LANS	3342	
ARB	3631	
TD	3636	

Casing
 10" 350
 7" 3621
 PU 2650' oil/12 hrs

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11-11-37