

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22904-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 4-11S-17W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ROY CARMICHAEL Well #: 9  
County: ELLIS Total Vertical Depth: 3488 feet

Operator License No.: 30537  
Op Name: VENTURE RESOURCES, INC.  
Address: 2110 S. GILPIN PO BOX 101234  
DENVER, CO 30250

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3470	0	w/150 sxs cmt
SURF	8.625	202	0	w/135 sxs cmt

\$ 113<sup>36</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2005 2:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN CARLEY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: 09/26/2005 - Ordered 265 sxs 60/40 pozmix - 10% gel - 500# hulls.  
09/27/2005 - Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Backside squeezed with 275 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2005 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

09/26/2005 - Ran tubing to 805' - hit bridge.  
Swift Services had to circulate down each joint to 1005'.  
Ran tubing to 1505'.  
Swift Services pumped 240 sxs 60/40 pozmix - 10% gel with 500# hulls - good circulation.  
Pulled to 830' - pumped 25 sxs cement.  
PTOH.  
09/27/2005 - Ran tubing in hole - tagged cement at 930'.  
Swift Services pumped 85 sxs 60/40 pozmix - 10% gel with 500# hulls - circulated cement.  
PTOH. Topped off with 30 sxs cement - casing full.  
Hooked up to backside - instant 500#.  
Note: Salt Section and Dakota open.

Perfs:

Top	Bot	Thru	Comments
3109	3362		

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED  
DATE 10-03-05  
INV. NO. 200606058.3

RECEIVED  
OCT 03 2005

Form CP-2/3

KCC WICHITA

SEP 28 2005

LIBERTY ENTERPRISES, INC. #9 ROY CARMICHAEL 4-11-17W  
 308 W. MILL PLAINVILLE, KS 67663 SE SW SE  
 CONTR PIONEER DRG. CTY ELLIS

GEOL \_\_\_\_\_ FIELD UPPER TURKVILLE NW  
 E 1856 KB CM 2/24/82 CARD ISSUED 5/13/82 IP P 10 B0 & 15 BWPD  
 1851 GL PENN 3362-3388  
 API 15-051-22,904

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		763	+1093
TOP		2813	- 957
HEEB		3045	-1189
TOR		3066	-1210
LANS		3088	-1232
BKC		3324	-1468
ARB		3456	-1600
RTD		3488	-1632

8-5/8" 202/135sx, 4 1/2" 3470/150sx  
 NO DST'S  
 MICT - CO, PF (PENN) 26/3362-3388,  
 AC 1500G (15% MA), TSTD, RE-AC 1000G,  
 (15%), TSTD, POP, P 10 B0 & 15 BWPD,  
 3/28/82

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

IMAGED