

To:

STATE CORPORATION COMMISSION  
 Wichita State Office Bldg. - PLUGGING SECTION  
 130 S. Market, Room 2078  
 Wichita, Kansas 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address \_\_\_\_\_

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

API NUMBER 15-121-19908 0000  
 NWNNNW Sec/Twp/Rge 26-17S-22E  
5131 feet from south section line  
5122 feet from east section line  
 Lease/Well# DAY 10 ( GPS # ) B2  
 County MIAMI  
 Well Total Depth 355 EST feet  
 Production Pipe: 2 Size Feet 355 EST  
 Surface Casing: 8 Size Feet 20 EST  
 E 03132 D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670Address: 19245 FORD ROAD CHANUTE, KS. 66720Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 27 Month: JULY 2005Plugging proposal received from: MIKE KEPLEYCompany Name: KEPLEY WELL SERVICE Phone: 620-431-8945Were: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENTPlugging Proposal Received by: FRANK GUILFOYLEPlugging attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 28 Month: JULY 2005Actual Plugging Report: CLEAR ROAD TO WELL AND CLEAR LOCATION. RUN 3/4" INSIDE 2"TO 320 FT. RUN 1" OUTSIDE 2" TO 200 FT. WASH 1" TO 255 FT. WASH 3/4" INSIDE 2' TO 355 FT.PUMP PORTLAND CEMENT TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 92SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER 20050027019 GPS NUMBER DAY 10  
 (If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE  
 TECHNICIAN

RECEIVED

AUG 12 2005

KCC WICHITA

