

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23297-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 16-12S-14W
2310 feet from N Section Line, 1320 feet from E Section Line
Lease Name: BECKER Well #: 1
County: RUSSELL Total Vertical Depth: 3100 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W. 47TH STREET, STE 318
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	460	0	

#100⁷⁵

Well Type: OH-DH UIC Docket No: _____ Date/Time to Plug: 09/26/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JIM ROBINSON Company: DOUBLE EAGLE EXPLORATION Phone: (816) 531-0202

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2005 1:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Pumped 30 sxs 60/40 pozmix - 10% gel cement with 200# hulls.
Displaced with water to bottom of hole. Max. P.S.I. 800#.
Perfs at 2670'.
Cut off casing at 2352'.
Pulled to 1500' and pumped 70 sxs cement with 200# hulls.
Pulled to 900' and pumped 40 sxs cement with 100# hulls.
Pulled to 475' and pumped 30 sxs cement.
Pulled to 150' and circulated with 25 sxs cement.

Remarks: FRITZLER WELL SERVICE.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 10-3-05
INV NO 2006060578

RECEIVED
OCT 03 2005
KCC WICHITA

SEP 30 2005