

3 022792

15-207.19577.0600

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050048-047

SW,SE,NW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

2999 feet from south section line

3477 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00A.M. Day: 1 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL WAS OF MODERN CONSTRUCTION WITH 4 1/2" CASING TO

APPROXIMATELY 1000' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP

THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

X

TECHNICIAN

None

Operations Completed: Hour: 11:30AM Day: 1 Month: 8 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 925'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 68 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: (GPS SESSION PT. NO. 11) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:



TECHNICIAN

RECEIVED

AUG 12 2005

KCC WICHITA