

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21139-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 21-9S-26W
1480 feet from S Section Line, 2240 feet from E Section Line
Lease Name: FOSTER Well #: 1
County: SHERIDAN Total Vertical Depth: 4169 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	255		

\$ 135⁴⁹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/24/2005 8:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 09/24/2005 9:15 AM KCC Agent: HERB DEINES

Actual Plugging Report:


1st. Plug at 2350' w/25 sxs.
2nd. Plug at 1425' w/100 sxs.
3rd. Plug at 305' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 
(TECHNICIAN)

SEP 30 2005

INVOICED
DATE 10-3-05
INV. NO 2006060576

RECEIVED
OCT 03 2005
KCC WICHITA