

3 022811

15-207.23988.0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050048-044
SE,SE,NW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.
2878 feet from south section line
3175 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease/Well# MARTIN NO.2

Operator: STATE OF KANSAS

County WOODSON

Name & FEE FUND PLUGGING

Well Total Depth 1000' feet

Address _____

Production Pipe: 2" Size Feet 1000'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Surface Casing: 8" Size Feet 20'

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:30A.M. Day: _____ 9 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000" THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____ TECHNICIAN None _____

Operations Completed: Hour: 12:00P.M. Day: _____ 9 Month: 8 2005

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 147 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.08) (THIS WELL WAS NO.02 ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
AUG 12 2005
KCC WICHITA

Signed:

Clayton P. Titel
TECHNICIAN

Bm