

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-06832-00-00
Spot: NESWSE Sec/Twnshp/Rge: 33-18S-11W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MUSENBERG B Well #: 7
County: BARTON Total Vertical Depth: 3415 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W. 6TH ST
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3414	0	150 SX CMT
SURF	8.625	280	0	250 SX CMT

#110 99

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2005 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S NEMNICH Company: K&N PETROLEUM, INC. Phone: (620) 587-3361

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2005 11:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Could not get past 540' with tubing.
Ran tubing to 496'.
Circulated with 110 sxs 60/40 pozmix - 10% gel cement.
POOH.
Tied onto casing and pumped 50 sxs cement.
Backside circulated and shut in.
Pumped 55 sxs cement.
Max. P.S.I. 850#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3395	3398		
3164	3166		

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 9-28-05
INV. NO. 2006060512

RECEIVED
SEP 28 2005
KCC WICHITA

SEP 22 2005

I SERN BROS

#7 MUSENBERG 'B'

33-18-11W
NE SW SE

Contr. I SERN DRLG

BARTON County

E 1807RB Comm.

Comp. 12-12-58

IP

238 BOPD

PHY POT

Tops	Depth	Datum
Awk	377	+1230
HEEB	2950	-1143
KC	3085	-1278
ARB	3391	-1587
TD	3415	-1608

Casing

8" 280

5" 3414

PERF 3395-98: ACID 250: WTR &
SSO: PB: PERF 3164-66: 13
BOPH

ST PETER EAST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WACO: CEP