

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22408-00-00
Spot: E2NWSW Sec/Twnshp/Rge: 18-19S-12W
1980 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WONDRA Well #: 3
County: BARTON Total Vertical Depth: 3465 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3463	0	175 SX CMT
SURF	8.625	288	0	200 SX CMT

#112 61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2005 11:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Revd. from: DENNIS KLIMA Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2005 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Packer stuck in hole at 3269'.
Perforated at 1550' and 750'.
Ran tubing to 2500'.
Pumped 75 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled to 1250'.
Circulated with 55 sxs cement with 200# hulls.
POOH. Tied onto casing and pumped 100 sxs cement with 100# hulls.
Cement circulated up backside.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3441	3463		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

INVOICED

DATE 9-28-05

INV. NO. 2006060514

RECEIVED

SEP 28 2005

KCC WICHITA

SEP 22 2005

L. G. STEPHENSON & CO. INC.
 7701 E. KELL LOG #670
 WICHITA, KS 67207

#3 WONDRA


18-19-12W
 C E/2 NW SW

CONTR RED TIGER DRILG CO CTY BARTON

GEOL _____ FIELD FT ZARAH NORTH

K 1872 KB CM 6/18/81 CARD ISSUED 8/6/81 IP P 25 BOPD

API 15-009-22,408 LANS 3209-3232 OA



LOG TOPS	DEPTH	DATUM
<i>Act</i>	<i>740</i>	
TOP	2756	- 884
HEEB	3060	-1188
BR LM	3170	-1298
LANS	3183	-1311
BKC	3420	-1548
ARB	3439	-1529
LTD	3454	-1582
RTD	3465	-1593

8 5/8" 288/200sx; 4 1/2" 3463/175sx TOC 2463 FT
 DST (1) 3184-3244/60-45-60-45, REC 286' OIL, SIP 838-814#, FP 144-144#
 DST (2) 3240-3260/60-45-60-45, GTS/12" TSTM, REC 60' HO & GCM, 186' OCGW, 248' SOCGW, 372' WTR, SIP 432-438# FP 60-432#
 DST (3) 3400-3457/30-30-30-30, 77' OCM (25% OIL), SIP 933-876#, FP 96-96#
 MICT - CO, PF (LANS) 8/3209-11, 8/3216-18, 12/3223-25, 8/3230-32, SWB DRY AC 250 GAL, SWB 5BFPH, 90% OIL, R&T, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS