

3 022824

15-207. 19574-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050048-046

SW,SE,NW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

2871 feet from south section line

3594 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

RECEIVED

Operator: STATE OF KANSAS

AUG 22 2005

Name & FEE FUND PLUGGING

KCC WICHITA

Address

Lease/Well#

MARTIN NO.3 A

County

WOODSON

Well Total Depth

1000'

feet

Production Pipe:

2"

Size Feet 1000'

Surface Casing:

8"

Size Feet 20'

AB oil well

X

Gas Well

SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at:

Hour:

8:30A.M.

Day:

11

Month:

8

2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were:

THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH

OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent:

All

X

Part

None

Operations Completed: Hour:

10:30A.M.

Day:

11

Month:

8

2005

Actual Plugging Report:

3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS

TO 525'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 170 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.10) (THIS WELL WAS WELL NO.3 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bm