

3 022769

15-207-19586 00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-021

NW,SE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.

3605 feet from south section line

926 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well#

WILLIAMS NO.4 A

County

WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 750' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 750'

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE, INC.

Lic. #

3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 20 Month: 7 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE 2" CASING PARTED AT 450' AND THE TOP 450'

OF 2" CASING WAS REMOVED. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH

OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None ☐ X ☒

Operations Completed: Hour: 5:00P.M. Day: 20 Month: 7 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 8" SURFACE CASING TO 600'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE
SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS
FILLED FROM SURFACE. 230 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.5) (THIS WELL WAS NO.4 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED

Signed:

AUG 02 2005

KCC WICHITA

Clayton P. Titel
TECHNICIAN

pm