

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21315-00-00  
Spot: W2NENE Sec/Twnshp/Rge: 15-34S-23W  
660 feet from N Section Line, 1000 feet from E Section Line  
Lease Name: HAWKEYE Well #: 15-1  
County: CLARK Total Vertical Depth: 247 feet

Operator License No.: 33392  
Op Name: KEITH F. WALKER OIL & GAS CO., LLC  
Address: P.O. BOX 1725 219 STANLEY STREET  
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	78		

\$ 35<sup>00</sup>

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2005 10:00 AM  
Plug Co. License No.: 31572 Plug Co. Name: BIG A DRILLING LC  
Proposal Rcvd. from: BARRY JONES Company: KEITH WALKER OIL & GAS Phone: (580) 223-1575

Proposed Plugging Method: FILL FROM 200' TO 0' WITH CMT

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 09/21/2005 6:15 PM

WitnessType: COMPLETE (100%)  
KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMPED 200 SX CMT THROUGH 200' OF 1" PIPE. NO CIRCULATION. TRIED TO PULL 1" PIPE. RECOVERED 50' WITH 150' STUCK IN HOLE. WAIT 4 1/2 HOURS. TOC @ 70'. PUMPED 100 SX CMT WITH GOOD CIRCULATION TO SURFACE. PUMP AN ADDITIONAL 100 SX CMT WITH OVERFLOW RUNNING DOWN OUTSIDE OF CONDUCTOR PIPE. ADDED 4 SX HULLS TO GET CMT TO POOL AROUND PIPE.

Perfs:


Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: DP

**INVOICED**

DATE 9-27-05  
INV. NO. 2006060507

District: 0



Signed

Jerry W. Stapleton PIRT II  
(TECHNICIAN)

RECEIVED  
SEP 27 2005  
KCC WICHITA

CP-2/3