

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20635-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 28-30S-38W
2100 feet from S Section Line, 4000 feet from E Section Line
Lease Name: MATZEN Well #: 3-28
County: GRANT Total Vertical Depth: 2950 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2375		WITH 2 SX CMT
PROD	5.5	2946	885	WITH 800 SX CMT
SURF	8.625	657	0	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/26/2005 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2375' WITH 2 SX CMT. PLUG AT 1700' WITH 20 SX CMT. PLUG AT 675' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2005 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG SET CIBP @ 2375' WITH 2 SX CMT. 2ND PLUG PUMP 20 SX CMT AT 1700' INSIDE 5 1/2". 3RD PLUG CUT OFF AT 885'. PULL TO 675' & PUMP 50 SX CMT. 4TH PLUG PUMP 10 SX CMT AT 40'.

Perfs:


Top	Bot	Thru	Comments
2424	2738		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

INVOICED
DATE 9.27.05
INV. NO. 2006060509

District: 01



Signed

Jim Holland
(TECHNICIAN)

RECEIVED
SEP 27 2005
KCC WICHITA