

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00236-00-00
Spot: NWSESW Sec/Twnshp/Rge: 35-21S-13W
1039 feet from S Section Line, 3713 feet from E Section Line
Lease Name: DRACH Well #: 1
County: STAFFORD Total Vertical Depth: 3665 feet

Operator License No.: 6458
Op Name: POOR BOY CORPORATION
Address: 582 S E 50TH AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3100		
PROD	5.5	3661	0	
SURF	8.625	239		

11
A119

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2005 11:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: LOREN HADDEN Company: POOR BOY CORPORATION Phone: (620) 793-7223

Proposed Plugging Method: SET CIBP @ 3100'. PERFORATE AT 700'. RUN TUBING TO 700'. PUMP CMT UNTIL IT CIRCULATES UP 8 5/8" X 5 1/2" ANNULUS & 5 1/2" CASING. PULL TUBING & TOP OFF WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2005 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

HOLES IN CASING AT 340'. SET CIBP @ 3100'. PERFORATED 5 1/2" CASING AT 700'. RUN 2 3/8" TUBING INTO 700'. PUMPED DOWN 2 3/8" TUBING WITH 10 SX GEL & 240 SX CMT. CMT CIRCULATED UP 2 3/8" X 5 1/2" ANNULUS & 5 1/2" X 8 5/8" ANNULUS. PULLED TUBING OUT & TOPPED OFF 5 1/2" CASING WITH 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3513	3523		
3484			
3363	3365		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

INVOICED
DATE 9-28-05
INV. NO 2006060 513

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
SEP 28 2005
KCC WICHITA

Form CR-23