

3 022796

15-001-24730 000

To: *

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050040-006

SE, SW, SE 1/4

Sec/Twp/Rge S.28-T.25S.-R.18E.

1634 feet from south section line

1417 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well#

DOTY NO.7

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 875' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 7" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 27 Month: 7 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-431-9212

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL

WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 5:00P.M. Day: 27 Month: 7 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

42 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

NOTE: THIS WAS PROBABLY WELL NO.7 (API NO.15-15-001-24,730)

Remarks: (GPS SESSION PT. NO.6) (THIS WELL WAS NOT ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


 TECHNICIAN

 RECEIVED
 AUG 12 2005
 KCC WICHITA