

3 022832

15-001. 247720000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: 12 Month: 8 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HADBEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOCIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐Operations Completed: Hour: 10:00A.M. Day: 12 Month: 8 2005Actual Plugging Report: AN INSERT PUMP HAD BEEN LOST IN THE BOTTOM OFTHE 2" CASING. 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT WAS PUMPEDINTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 42 SACKS OFCEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO. 1) (THIS WELL BELIEVED TO BE NO. 9 15-001-24772))

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

AUG 29 2005

KCC WICHITA

Bm