

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22470-00-00
Spot: SWSESE Sec/Twnshp/Rge: 17-19S-9W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: LINK Well #: K-1
County: RICE Total Vertical Depth: 3273 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S. BOSTON AVE., SUITE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250		

37
\$106

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2005 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: TIM GULICK Company: C & G DRILLING, INC. Phone: (620) 583-4306

Proposed Plugging Method: 35 sxs top of Arbuckle; 35 sxs @ 1200'; 35 sxs @ 800'; 35 sxs @ 300'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 08/30/2005 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

A 35 sacks of cement plug was spotted at the top of the Arbuckle at 3270'. The drill pipe was pulled to 1200' and spotted with 35 sacks of cement. The drill pipe was pulled to 800' and spotted with 35 sacks of cement. The drill pipe was pulled to 300' and spotted with 35 sacks of cement. The drill pipe was pulled to 60' and cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

Copeland Cement

60/40 posmix with 4% gel


RECEIVED
KCC DISTRICT #2
SEP - 1 2005
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 9-29-05
INV. NO. 2006060538

RECEIVED
SEP 29 2005
KCC WICHITA

Form CP-2/3