

15-207-19592 ooo

API NUMBER CONTROL NO. 20050019-050

SE,SE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.

3168 feet from south section line

591 feet from east section line

591 feet from east section line

Lease/Well# WILLIAMS NO. 31

County WOODSON

Well Total Depth 750' feet

Production Pipe:	Size	Feet
------------------	------	------

Surface Casing: 8" Size Feet 20'

AB oil well X	Gas Well	SWD Well/ Input Well	D & A
---------------	----------	----------------------	-------

Plugging Contractor: K-W OIL WELL SERVICE, INC. Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KS. 66720

Company to plug at: Hour: 9:00A.M. Day: 7 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 8" SURFACE CASING ONLY BELOW SURFACE. 12'

OF SURFACE CASING WAS INSTALLED TO BRING THE WELL TO SURFACE. THE PLUGGING

PROPOSAL WAS TO DRILL OUT THE WELL AND TO CIRCULATE AS MUCH OF THE WELL

AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

		TECHNICIAN	
Plugging attended by Agent:	All	Part	None X
Plugging attended by Agent:	All	Part	None X

Operations Completed: Hour: 12:00P.M. Day: 7 Month: 9 2005

Actual Plugging Report: THE WELL WAS DRILLED OUT TO 400'. 1" PIPE WAS

RAN INTO THE WELL TO 400'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE WELL AT SURFCE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 294 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.31) (THIS WELL WAS NOT SHOWN ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Fild
TECHNICIAN

RECEIVED
SEP 21 2005
KCC WICHITA

