

3 022844

15.207.19597.000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-051

NE,SE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.

3526 feet from south section line

166 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Lease/Well# WILLIAMS NO.22County ~~ALLEN~~Well Total Depth 750' feet

Production Pipe: _____ Size Feet _____

Surface Casing: 12" Size Feet 20'Plugging Contractor: K-W OIL WELL SERVICE, INC.Lic. # 3097Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: _____ 30 Month: 8 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: NO CASINGS WERE EVIDENT IN THIS WELL. 20' OF 12" SURFACE CASING WAS
INSTALLED IN THE WELL. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE WELL AND
TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None ☒Operations Completed: Hour: 10:00A.M. Day: _____ 30 Month: 8 2005Actual Plugging Report: THE WELL WAS DRILLED OUT TO 275'. AT THAT DEPTH

IRON HALTED PROGRESS. 1" PIPE WAS RAN INTO THE WELL TO 275'. CEMENT WAS
PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING
AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM
SURFACE. 200 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.22) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
SEP 09 2005
KCC WICHITA