

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121.01059.000
NWSWSW Sec/Twp/Rge 23-17S-22E
1174 feet from south section line
5060 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# DUN 10 (GPS #) B6
County MIAMI
Well Total Depth 365 EST feet
Production Pipe: 2 Size Feet 365 EST
Surface Casing: 7 Size Feet 20 EST.

Name & FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: _____ 1 Month: AUGUST 2005

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-8945

Were: FILL WELL FROM TD TO SURFACE WITH PORTLAND CEMENT

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All _____ Part X TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: _____ 18 Month: AUGUST 2005

Actual Plugging Report: CLEAR JUNK FROM AROUND WELL. CLEAR ROAD. RUN 3/4" INSIDE 2" TO 340 FT. WASH 1" OUTSIDE 2" TO 270 FT. WASH INSIDE 2" TO 365 FT. PUMP PORTLAND CEMENT TO SURFACE INSIDE 2" AND OUTSIDE 2". PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 84 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER 20050027009 GPS NUMBER DUN 10
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
SEP 09 2005
KCC WICHITA

Signed: FRANK GUILFOYLE
TECHNICIAN

