

15-163-00342-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SE NW

SEC. 52 TWP. 7 RGE. 19 *W*

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schoeller

Operator Deep Rock Oil Address Wichita, Kans

Field _____ County Rooks

Total Depth 3405 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 136' circulated with cement.

Circulated hole with heavy rotary mud, pushed wood plug to
400', displaced 30 sax cement through drill pipe, pushed wood plug
to 146', displaced 20 sax cement through drill pipe, rotary mud to
25', set wood plug and filled hole to -0- with cement.

PLUGGING
FILE SEC 52 T 7 R 19 *W*
BOOK PAGE 72 LINE 36

Jedson Terry
District Conservation Agent **E D**
Date 4-7-51

APR 10 1951
CONSERVATION DIVISION
Wichita, Kansas
4-10-51