

15-193-20042-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
6115 23 1972
CONSERVATION DIVISION
Wichita, Kansas

8-23-72

Operator's Full Name Murfin Drilling Co., Patrick Petroleum & Carnahan.
 Complete Address 617 Union Center, Wichita, Kansas.
 Lease Name Goetsch Well No. 1
 Location Appr:-CSE-SW Sec. 35 Twp. 6 Rge. (E) (W) 36
 County Thomas Total Depth 3045'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Murfin Drilling Company,
 Address 617 Union Center, Wichita, Kans. License No.
 Operation Completed: Hour 12:30 PM Day 17 Month 8 Year 1972

The above well was plugged as follows:

293'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 110 Cu. Ft. cement
thru DP from 1925' to 1600'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dinkel
Well Plugging Supervisor

DATE 8/23/72
INV. NO. 6219-u