

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20036-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas

4-5-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name McCormick Theological Seminary Well No. 1

Location CNW-NW Sec. 35 Twp. 6 Rge. (E) (W) 36

County Thomas Total Depth 4200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 3:30 PM Day 31 Month 3 Year 1971

The above well was plugged as follows:

303'--8 5/8" Surface casing cement circulated with 250 Sx.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru

DP from 1250' to 925'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from 310'

to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of

cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Diehls
Well Plugging Supervisor

INVOICED

DATE 4/6/71

INV. NO. 3504-W