

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20022-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1969

CONSERVATION DIVISION
Wichita, Kansas

9-19-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Graves Drilling Company, Incorporated,

Complete Address 505 Union Center Building, Wichita, Kansas.

Lease Name Roulier Well No. 1

Location 300' N. of CSE-NE Sec. 35 Twp. 6 Rge. (E) (W) 36

County Thomas Total Depth 4932'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 12:15 AM Day 16 Month 9 Year 1969

The above well was plugged as follows:

320'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1900' and displaced 100 Sx. cement thru
DP from 1900' to 1575'. Pulled DP to 330' and displaced 20 Sx. cement thru DP from
330' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/19/69
INV. NO. 561-W