

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21, 205-00-00

245 North Water
Wichita, KS 67202

Operator's Full Name OXFORD EXPLORATION COMPANY.

Complete Address 1550 DENVER CLUB, BLDG. DENVER, COLORADO.

Lease Name STAMMONS Woodlugs Well No. # 13-133

Location SW-SW-SW Sec 13 Twp. 7 Rge. 20 (East) (West)

County ROCKS Total Depth 3657 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor MURFIN DRILLING COMPANY. (BERNIE MEYER)

Address 617 UNION CTR, BLDG. - WICHITA, KS License No. _____

Operation Completed: Hour: 7:00 PM Day: 29 Month: JAN Year: 19 81

The above well was plugged as follows:

8 5/8" 176 FE SP. CMT w/ 145 ST COMMON QUICK SET.
ORDERED 110 ST 50/50 Pozmix 6% GEL. + 8 5/8" PLUG. (ENV. 2044)
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1 ST PLUG. @ 860 FE w/ 70 ST CMT.
2 ND PLUG. @ 240 FE w/ 25 ST CMT.
3 RD PLUG. -> SOLID BRIDGE @ 40 FE w/ 10 ST CMT.
5 ST IN RAT HOLE.

CEMENTED BY FILLED CMT.

CONSERVATION DIVISION
Wichita, Kansas
FEB 21, 1981
FEB - 8 1981

I hereby certify that the above well was plugged as herein stated.

DATE 2-26-81
INV. NO. 4699-W

Signed: Maxwell Schmitt
Conservation Division Agent