

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-181-2 0018-0000

SEE 2505  
9-25-75

Operator's Full Name Dreiling Oil Inc.

Complete Address RT. 2: Victoria Ks.

Lease Name Hartley "A" Well No. #1

Location C-SE-SE Sec. 6 Twp. 6 Rge. 37 (E) (W)

County Sherman. Total Depth 4730.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Dreiling Oil Inc.

Address RT. #2 - Victoria Ks. License No. \_\_\_\_\_

Operation Completed: Hour 10:00 AM Day 9 Month Sept. Year 1975

The above well was plugged as follows:

KB. 3055 - Dak Top. 1550. S.P. 312' of 8 5/8" cwc. 285 sx

Pumped down. Drillstem

70 sx cem. 50/50 Pozmix 6% Gel @ 1600'

20 " " " " " " 300'

Build Bridge to 40'

10 sx Cem. 50/50 Pozmix 6% Gel. 40' to 0.

Sum Cementing

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-26-75

INV. NO. 1967-W

Signed: Gilbert Balthazar  
Well Plugging Supervisor