

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-181-20013-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 30 1974  
CONSERVATION DIVISION  
Wichita, Kansas

4-30-74

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Hartley Well No. 2

Location CS/2 Sec. 3 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4840'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 11:00 AM Day 27 Month 4 Year 1974

The above well was plugged as follows:

367'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1850'.

Circulated hole with heavy mud. Pulled DP to 2075' and displaced 110 Cu. Ft. cement  
thru DP from 2075' to 1750'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru  
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 5/1/74  
INV. NO. 9017-W