

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-181-05053-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 20 1967  
2-20-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Phillips Petroleum Company,

Complete Address: P.O. Box #287, Great Bend, Kansas.

Lease Name Hartley Well No. A-4

Location CNW-SE Sec. 3 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4996

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 346

Operation Completed: Hour 6:00PM Day 15 Month 2 Year 1967

The Above well was plugged as follows:

378'--9 5/8" Surface pipe, cement circulated.  
4861'--7" OD Production string cemented, Temp. Survey shows top of cement  
@3090'. Well plugged back to 4796'. Top perforations from 4778' to 4784'.  
Sanded well back to 4760' and set 5 Sx. cement with dump bailer.  
Pulled 7" casing, set rock bridge @ 400' and filled hole to 250' using 3  
yards Redi-Mix. Filled hole with mud to 50' and from 50' to bottom of  
cellar with Redi-Mix using 1 yard.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Fichels  
Well Plugging Supervisor

DATE 2-20-67  
INV. NO. 4795-10