

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-181-05052-00-00

FEB 26 1963
2-26-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Co.

Complete Address: Box #779, Great Bend, Kansas.

Lease Name Hartley Well No. A-3

Location SE-SE Sec. 3 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4972

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 6:45P Day 23 Month 2 Year 1963

The Above well was plugged as follows:

363' 95/8" surface pipe, cement circulated. 7" production string set @ 4970', plugged back to 4516', perforated from 4480' to 4486'. Sanded wellback to 4465' and set 4 Sx cement w/dump bailer, Pulled 7", loaded hole with salt water to 552'. Set wood & rock bridge from 552' to 540', 25 sacks cement from 540' to 490', heavy gel mud from 490' to 390' (5 sacks), 25 sacks cement from 390' to 340'. (This well left as a water well for land owner). (Cement & cementing & mudding operations performed by Halliburton Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2/26/63

INV. NO. 6650-U