

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-181-05041-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

2-16-71

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #287, Great Bend, Kansas.

Lease Name Llanos Well No. 3

Location CNE-NW Sec. 10 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company,

Address Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 12:45 PM Day 12 Month 2 Year 1971

The above well was plugged as follows:

360'--9 5/8" Surface casing, cement circulated. (8 3/4" Hole).

4844'--7" OD Production casing cemented on bottom with 230 Sx. Well plugged back to 4657'. Perforations from 4436' to 4652'.

Ran 2" tubing to bottom and displaced 70 Sx. cement thru tubing. (Top of cement @ 4177'). Pulled 7" OD Casing(3300') and squeezed well initially with 5 sacks bulls and 19 sacks gel and followed with 150 Cu. Ft. cement from 2125' to 1775' then 42 sacks gel from 1775' to 375' and followed with 35 Cu. Ft. cement from 375' to 300' then 9 sacks gel from 300' to 25' and finally 15 Cu. Ft. cement from 25' to bottom of cellar.

Maximum pump-in pressure-400#. Final Shut@in pressure-300#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/17/71
INV. NO. 3349-W