

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

13-181-05042-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1974  
12-20-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Phillips Petroleum Co.  
Complete Address Box 287, Great Bend, Kansas  
Lease Name Llanos Well No. 4  
Location C NE NE Sec. 10 Twp. 66 Rge. (E) (W) 37  
County ~~Cherokee~~ Sherman Total Depth 5014'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Kelso Pipe Pulling  
Address Box 176, Chase, Kansas License No. 683  
Operation Completed: Hour 3:30 P Day 17 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 5014' 9 5/8 csg set at 374' cwc

7" csg set at 4972' cw 105 sx cem. PBD 4533' PFS (4442-4448)

Set 7" wood plg 4400' -15' sd -6 sx cem W/dump bailer. (4400-4350)

Cutoff & recovered 2711' of 7" csg.

Pumped down 9 5/8 csg with 20 sk gel & water W/200 lbs hulls -Gel brokeout around

outside of 9 5/8 csg. Ran 13 jts tbg set at 388' -displaced 50 sk cem. Pulled

11 jts tbg -circulated 27 sx cement from 60' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/24/74

INV. NO. 518-W

Signed: Leo F. Massey  
Well Plugging Supervisor