

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-181-05039-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-27-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Phillips Petroleum Company,

Complete Address: Box # 287, Great Bend, Kansas.

Lease Name Llanos Well No. 1

Location W/2-NW-NE, Sec. 10 Twp. 6 Rge. (E) (W) 37

County Sherman Total Depth 4960

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 11:45AM Day 22 Month 5 Year 1968

The Above well was plugged as follows:

370'--8 5/8" Surface pipe, cement circulated.  
5000'--4 1/2" Drill pipe set for production string, cemented on bottom with 160 Sx. Stage collar set @ 2791' with cement circulated to surface with 350 Sx. Top perforations from 4804' to 4812'.

Sanded well back to 4750' and set 2 Sx. cement with dump bailer. Pushed plug to 1650', sanded well back to 1625' and set 2 Sx. cement with dump bailer. Let plugs set overnight, bailed hole dry and filled to surface using 6 yards Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 5/27/68  
INV. NO. 7821-W