

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-095-21988-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation
(owner/company name)

KCC LICENSE # 5003
(operator's)

6/10/06

ADDRESS: 8080 E. Central, Suite 300 CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: Elliott GU Twin WELL#: 1-30 Section 30 Township 30s Range 9w

50' N & 70' E of S/2 N/2 SW SPOT LOCATION/QQQQ COUNTY: Kingman

1700 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

1390 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 213' KB CEMENTED WITH 250 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1700 G.L. 1709 K.B. T.D. 4755 PBDT _____ Anhydrite Depth Not Know
(Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE YES

PROPOSED METHOD OF PLUGGING:
Received plugging orders 09/16/05 at 11:00 am from Dwayne Krueger. Heavy mud in hole and between plugs.
Plugged with 35 sx at 1300', 35 sx at 1000', 35 sx at 260' and 25 sx at 60'. Plugged rathole with 15 sx and
mousehole with 10 sx. Total cement 155 sx 60/40 Poz, 4% Gel. Plugging completed at 3:00 pm on 09/18/05
by Acid Services, Ticket # 11713. Sterling reported plugging to KCC on 09/19/05.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary M. Talbott Phone#: (620) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142

(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 3:00 pm on September 19, 2005.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 09/18/05 AUTHORIZED OPERATOR OR AGENT: _____

RECEIVED
SEP 22 2005
KCC WICHITA
Gary M. Talbott
Gary M. Talbott, Agent for Operator

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Elliott GU Twin 1-30

LOCATION: 50' N & 70' E of S/2 N/2 SW
API: 15-095-21988-0000

Section 30 T 30s R 9w
Kingman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 09/09/05
COMPLETED: 09/18/05

TOTAL DEPTH:

DRILLER	4755	FEET
LOGGER	4748	FEET

Ground Elevation: 1700
KB Elevation: 1709

LOG

0 -	2 FEET	Top Soil
2 -	8 FEET	Clay
8 -	15 FEET	Sand and Gravel
15 -	180 FEET	Sand and Gravel
180 -	920 FEET	Redbeds
920 -	1420 FEET	Shales and Salt
1420 -	4755 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 7:30 pm on 09/09/05. Drilled 12-1/4" hole to 215'. Ran 5 joints of new 23# 8-5/8" casing, tally 202.07' set at 213.07' KB. Cemented with 250 sx 60/40 Poz, 2% Gel, 3% CC, 1/4# Celloflake. Plug down at 12:45 am on 09/10/05 by Acid Services, ticket #11771. Cement did circulate. Welded straps on bottom 2 jts, of SP, then welded collars on next 3 joints.

Plugging Information:

Plugged with 35 sx at 1300', 35 sx at 1000', 35 sx at 260' and 25 sx at 60'. Plugged rathole with 15 sx and mousehole with 10 sx. Total cement 155 sx 60/40 Poz, 4% Gel. Plugging completed at 3:00 pm on 09/18/05 by Acid Services, Ticket # 11713. Sterling reported plugging to KCC on 09/19/05.

DEVIATION SURVEYS

3/4 degree(s) at	215	feet
1 degree(s) at	4406	feet
2 degree(s) at	4755	feet

RECEIVED
SEP 22 2005
KCC WICHITA



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

McCoy Petroleum Corporation
8080 E. Central, Suite 300
Wichita, KS 67206

September 22, 2005

Re: ELLIOTT GU TWIN #1-30
API 15-095-21988-00-00
S2N2SW 30-30S-9W, 1700 FSL 1390 FWL
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



David P. Williams
Production Supervisor