

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 207-19<sup>351</sup>44-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7/1/24

Well Operator: Southern Star Central Gas Pipeline KCC License #: 33097  
(Owner / Company Name) (Operator's)

Address: 4700 Hwy. 56 P.O. Box 20010 City: Owensboro

State: Kentucky Zip Code: 42304-0010 Contact Phone: ( 270 ) 852 - 4489

Lease: Piqua Well #: O-2 Sec. 3 Twp. 25 S. R. 17 ☒ East ☐ West

NW - SW - Spot Location / QQQQ County: Woodson

1960 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

4302 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well  
☐ SWD Docket # ☐ ENHR Docket # ☒ Other: Gas Storage

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 10" Set at: 11 ft Cemented with: NA Sacks

Production Casing Size: 2" Set at: 916 ft Cemented with: 30 Sacks

List (ALL) Perforations and Bridgeplug Sets:

Elevation: (☐ G.L. / ☐ K.B.) T.D.: 922 PBTD: Anhydrite Depth: (Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

Run 1" tubing down back side of 2" pipe and wash down to bottom. Run separate string of 1" inside of 2" to bottom of hole and fill with cement from bottom up.

Once hole is full, tie onto 2" and squeeze cement with some pressure. Then fill back side of 2" from bottom to top until cement shows at surface.

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why? Attached is well record and notes from well file. No ACO-1 in well file.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations:

Bernie Rockers Phone: ( 785 ) 448 - 4816

Address: P.O. Box 550 City / State: Welda, KS 66091

Plugging Contractor: Splane Pulling and Roustabout Service KCC License #: 6372

Address: P.O. Box 386, Chanute, KS 66720 Phone: ( 620 ) 431 - 1359  
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?):

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/4/2005 Authorized Operator / Agent: D. Mark Rouse Staff Geologist  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
6/10/05 OCT 07 2005  
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Southern Star Central Gas Pipeline, Inc.  
4700 Highway 56  
Owensboro, KY 42301

October 11, 2005

Re: PIQUA #0-2  
API 15-207-19351-00-01  
NWSW 3-25S-17E, 1960 FSL 4302 FEL  
WOODSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #3  
1500 W. 7th  
Chanute, KS 67220  
(620) 432-2300

Sincerely



David P. Williams  
Production Supervisor