

RECEIVED
OCT 03 2005
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 151-22159-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: KENNETH S. WHITE KCC License #: 30128 6/04

Address: 2400 N. Woodlawn, Suite 115 City: Wichita

State: Kansas Zip Code: 67220 Contact Phone: (316) 682 - 6300

Lease: Green Well #: 1 Sec. 33 Twp. 26 S. R. 12 East West

E/2 - NE - NW Spot Location / QQQQ County: Pratt

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: None Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10-3/4" Set at: 316 Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 4429 Cemented with: 135 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf @ 4332-35, CIBP @ 4330, Perf @ 4317-20, CIBP @ 4302, Perf @ 4283-88, CIBP @ 4280, Perf @ 4222-26

Elevation: 1907 (G.L. / K.B.) T.D.: 4429 PBTD: 4280 Anhydrite Depth: 1260' - 1920'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 4150' and dump 5 sx cement, shoot casing for recovery, pull casing and plug @ 1920' with 50 sx cement, 75 sx cement @ 330', 25 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Filed with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Herb Durant Phone: (620) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge, KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529 9/04

Address: P.O. Box 467, Chase KS 67524 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/26/05 Authorized Operator / Agent: Kenneth S. White
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White, Kenneth S.
2400 N. Woodlawn, Suite 115
Wichita, KS 67220

October 06, 2005

Re: GREEN #1
API 15-151-22159-00-00
E2NENW 33-26S-12W, 660 FNL 2310 FWL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888