

RECEIVED  
OCT 03 2005  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 151-22137-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_.

Well Operator: KENNETH S. WHITE KCC License #: 30128  
(Owner / Company Name) (Operator's)

Address: 2400 N. Woodlawn, Suite 115 City: Wichita

State: Kansas Zip Code: 67220 Contact Phone: (316) 682 - 6300

Lease: Zink Well #: 1 Sec. 4 Twp. 26 S. R. 11  East  West

NW - SE - SE - \_\_\_\_\_ Spot Location / QQQQ County: Pratt

990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 10-3/4" Set at: 255 Cemented with: 225 Sacks

Production Casing Size: 5-1/2" Set at: 4166 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4010-4030', 4032', 4034', 4036', 4038-4044', all one shot per foot

Elevation: 1840 ( G.L. /  K.B.) T.D.: 4170 PBTD: 4145 Anhydrite Depth: 1110' - 1780'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 3900' and dump 5 sacks cement, shoot casing for recovery, pull casing and plug @ 650' w/50 sx cement, 70 sx @ 250', 15 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Sent in when well drilled

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Herb Durant Phone: (620) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529

Address: P.O. Box 467, Chase KS 67524 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/30/05 Authorized Operator / Agent: Kenneth S. White  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

David P. Williams  
Production Supervisor

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White, Kenneth S.  
2400 N. Woodlawn, Suite 115  
Wichita, KS 67220

October 06, 2005

Re: ZINK #1  
API 15-151-22137-00-00  
NWSESE 4-26S-11W, 990 FSL 990 FEL  
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888